

BILANS ROBÓT ZIEMNYCH - Linia trasowania oś							
Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu	Obj. netto
0+000.00	0.76	0.00	0.00	0.00	0.00	0.00	0.00
0+011.97	3.46	0.61	25.27	3.65	25.27	3.65	21.62
0+025.00	3.83	1.27	47.51	12.22	72.78	15.86	56.92
0+050.00	5.99	1.51	122.70	33.76	195.48	49.62	145.86
0+075.00	4.23	2.56	127.70	49.71	323.18	99.33	223.84
0+100.00	2.59	0.43	85.24	36.53	408.42	135.87	272.55
0+125.00	3.07	1.28	70.84	20.94	479.26	156.80	322.46
0+150.00	4.71	0.26	97.10	19.10	576.35	175.91	400.45
0+175.00	6.87	0.99	144.98	15.73	721.33	191.64	529.69
0+200.00	11.30	0.43	227.84	17.80	949.17	209.44	739.74
0+225.00	15.76	0.00	339.74	5.32	1288.91	214.76	1074.15
0+250.00	4.23	0.23	251.65	2.82	1540.56	217.58	1322.98
0+275.00	8.80	0.00	160.28	2.89	1700.84	220.47	1480.37
0+300.00	5.94	0.33	180.92	4.13	1881.76	224.60	1657.16
0+325.00	4.74	0.22	131.05	6.92	2012.81	231.52	1781.29
0+350.00	6.38	0.00	139.07	2.74	2151.89	234.27	1917.62
0+375.00	7.72	0.00	176.28	0.00	2328.17	234.27	2093.90
0+400.00	6.27	0.00	174.91	0.00	2503.08	234.27	2268.81
0+425.00	6.54	0.00	160.20	0.00	2663.27	234.27	2429.00
0+450.00	3.77	0.18	128.71	2.26	2791.98	236.53	2555.45
0+475.00	4.57	0.05	104.33	2.92	2896.32	239.45	2656.86
0+500.00	1.21	1.11	72.34	14.49	2968.66	253.94	2714.72
0+525.00	1.69	1.21	36.41	28.87	3005.07	282.82	2722.25
0+550.00	1.70	0.73	42.51	24.20	3047.58	307.02	2740.56
0+575.00	2.96	0.08	58.29	10.20	3105.87	317.21	2788.65
0+600.00	3.71	0.01	83.42	1.12	3189.28	318.34	2870.95
0+625.00	3.52	0.17	90.34	2.18	3279.63	320.52	2959.11
0+650.00	1.16	1.22	58.45	17.29	3338.08	337.81	3000.27
0+675.00	2.29	0.14	43.05	17.01	3381.13	354.82	3026.31
0+700.00	3.40	0.01	71.05	1.97	3452.18	356.79	3095.39
0+725.00	4.06	0.00	93.26	0.18	3545.44	356.97	3188.47
0+750.00	2.88	0.05	86.76	0.60	3632.20	357.56	3274.63
0+775.00	2.89	0.07	72.06	1.52	3704.25	359.09	3345.16
0+800.00	3.01	0.05	73.75	1.52	3778.00	360.60	3417.40
0+825.00	3.46	0.12	80.87	2.08	3858.87	362.69	3496.18
0+850.00	2.84	0.14	78.70	3.31	3937.57	366.00	3571.57
0+875.00	1.82	0.35	58.22	6.26	3995.79	372.26	3623.53
0+900.00	1.38	0.66	39.96	12.70	4035.74	384.96	3650.78
0+925.00	3.31	0.14	58.63	10.03	4094.38	395.00	3699.38
0+950.00	2.26	0.72	69.56	10.83	4163.93	405.83	3758.10
0+975.00	2.98	0.28	65.43	12.51	4229.37	418.33	3811.03
1+000.00	4.48	0.00	93.29	3.46	4322.66	421.80	3900.86
1+025.00	3.97	0.00	105.62	0.02	4428.28	421.82	4006.46
1+050.00	4.02	0.00	99.92	0.00	4528.20	421.82	4106.38
1+075.00	2.72	0.11	84.26	1.41	4612.46	423.23	4189.23
1+100.00	2.58	1.54	66.26	20.61	4678.71	443.84	4234.87
1+125.00	0.33	2.17	36.46	46.28	4715.17	490.12	4225.05
1+150.00	0.00	5.67	4.17	98.01	4719.34	588.13	4131.21
1+182.81	6.16	0.00	101.09	93.08	4820.43	681.21	4139.22
1+200.00	5.72	1.28	102.13	10.96	4922.55	692.17	4230.38
1+225.00	2.57	2.79	103.69	49.93	5026.25	742.10	4284.15
1+250.00	7.45	1.62	125.39	53.88	5151.64	795.98	4355.66
1+275.00	1.97	2.84	117.83	55.33	5269.46	851.30	4418.16
1+300.00	1.56	2.91	44.17	67.65	5313.64	918.95	4394.68
1+325.00	2.32	0.94	48.44	47.52	5362.08	966.47	4395.61
1+350.00	2.80	0.56	63.95	18.55	5426.03	985.02	4441.01
1+375.00	3.04	0.30	73.04	10.76	5499.07	995.77	4503.30
1+400.00	3.24	0.65	78.53	11.82	5577.60	1007.59	4570.00
1+425.00	2.86	1.14	76.27	22.40	5653.87	1030.00	4623.88
1+450.00	2.76	0.09	70.21	15.41	5724.09	1045.41	4678.68
1+475.00	4.07	0.00	85.30	1.12	5809.39	1046.53	4762.86
1+500.00	4.29	0.00	104.42	0.00	5913.81	1046.53	4867.28
1+525.00	3.20	0.03	93.54	0.36	6007.36	1046.90	4960.46
1+550.00	2.57	0.12	72.07	1.86	6079.43	1048.75	5030.68
1+575.00	1.92	0.32	56.12	5.53	6135.55	1054.28	5081.27
1+600.00	1.92	0.45	47.98	9.70	6183.53	1063.98	5119.54
1+625.00	3.16	2.30	63.43	34.43	6246.96	1098.41	5148.55
1+650.00	3.30	2.47	80.79	59.62	6327.75	1158.03	5169.72
1+675.00	3.59	2.19	86.24	58.19	6413.99	1216.22	5197.76
1+700.00	4.02	1.86	95.10	49.11	6509.09	1265.34	5243.76
1+725.00	3.23	2.15	90.47	48.70	6599.56	1314.03	5285.53
1+750.00	4.47	1.33	96.22	42.26	6695.78	1356.29	5339.49
1+770.77	4.07	0.45	88.73	17.93	6784.51	1374.22	5410.29
1+800.00	3.26	0.84	107.15	18.84	6891.65	1393.06	5498.59
1+814.70	3.62	0.83	50.59	12.26	6942.24	1405.33	5536.92
1+825.00	3.56	0.75	36.98	8.15	6979.22	1413.47	5565.75
1+850.00	3.46	0.07	87.66	10.32	7066.88	1423.79	5643.09
1+875.00	3.46	0.00	86.43	0.88	7153.31	1424.67	5728.64
1+900.00	3.70	0.00	89.47	0.00	7242.79	1424.67	5818.11
1+905.54	3.79	0.00	20.73	0.00	7263.52	1424.67	5838.84

Wykopy (minus rozbiórka nawierzchni i podbudowę z bruku): 7263,52 - (0,04+0,02)x7616,00 = 5435,68 m3
Nasypy : 1424,67 m3