

Lp.	Podstawa	Opis i wyliczenia	j.m.	Poszcz.	Razem
1		PRACE TYNKARSKIE, MALARSKIE			
1 d.1	KNR-W 4-01 0701-05 piwnica	Odbicie tynków wewnętrznych z zaprawy cementowo-wapiennej na ścianach, filarach, pilastrach o powierzchni odbicia ponad 5 m ² $(2.75*2.42+2*(2.75+2.42)*2.06+1.86*2.98+2*(1.86+2.98)*2.06+5.14*4.46+2*(4.46+5.14)*2.06+1.97*2.81+2*(1.97+2.81)*2.06-1.1*1.2*1.7+1.6*1.68+2*2.5+4.86*3.31+2*(4.68+3.31)*2.06+1.3*1.6+2*(1.6+1.3)*2.06)$	m ² m ²	209.622	
				RAZEM	209.622
2 d.1	KNR 4-01 0108-11	Wywiezienie gruzu sprzymowanego samochodami samowyladowczymi na odległość do 1 km 209.622*0.03	m ³ m ³	6.289	
				RAZEM	6.289
3 d.1	KNR 4-01 0108-12	Wywiezienie gruzu sprzymowanego samochodami samowyladowczymi - za każdy następny 1 km 6.289	m ³ m ³	6.289	
				RAZEM	6.289
4 d.1	KNR 0-23 2611-03-ana- logia	Dwukrotne gruntowanie emulsją $(4.45*4.16+2*(4.45+3.8)*2.06+2.75*2.42+2*(2.75+2.42)*2.06+1.86*2.98+2*(1.86+2.98)*2.06+5.14*4.46+2*(4.46+5.14)*2.06+1.97*2.81+2*(1.97+2.81)*2.06-1.1*1.2*1.7+1.6*1.68+2*2.5+4.86*3.31+2*(4.68+3.31)*2.06+1.3*1.6+2*(1.6+1.3)*2.06)$	m ² m ²	262.124	
				RAZEM	262.124
5 d.1	KNR 0-23 2612-06 - analogia	Przyklejenie warstwy siatki na ścianach 262.124	m ² m ²	262.124	
				RAZEM	262.124
6 d.1	KNR 2-02 0803-03	Tynki wewnętrzne zwykłe kat. III wykonywane ręcznie na ścianach i słupach 262.124	m ² m ²	262.124	
				RAZEM	262.124
7 d.1	KNR 0-23 2611-01-ana- logia	Oczyszczenie i zmycie $(4.45*4.16+2*(4.45+3.8)*2.06+2.75*2.42+2*(2.75+2.42)*2.06+1.86*2.98+2*(1.86+2.98)*2.06+5.14*4.46+2*(4.46+5.14)*2.06+1.97*2.81+2*(1.97+2.81)*2.06-1.1*1.2*1.7+1.6*1.68+2*2.5+4.86*3.31+2*(4.68+3.31)*2.06+1.3*1.6+2*(1.6+1.3)*2.06)$	m ² m ²	262.124	
				RAZEM	262.124
8 d.1	KNR 0-23 2611-03-ana- logia	Dwukrotne gruntowanie emulsją 262.124	m ² m ²	262.124	
				RAZEM	262.124
9 d.1	KNR 4-01 1201-01-ana- logia	Dwukrotne malowanie farbami wapiennymi tynków wewnętrznych ścian 262.124	m ² m ²	262.124	
				RAZEM	262.124
10 d.1	KNR-W 4-01 1215-08	Mycie po robotach malarskich posadzek $4.45*4.16+2.75*2.42+1.86*2.98+5.14*4.46+1.97*2.81+4.86*3.31+1.3*1.6$	m ² m ²	77.336	
				RAZEM	77.336